

कार्यपालक अभियंता का कार्यालय,
ग्रामीण कार्य विभाग, कार्य प्रमंडल, झंझारपुर ।

पत्रांक 1552 झंझारपुर / दिनांक 02/09/2025

प्रेषक,

कार्यपालक अभियंता,
ग्रामीण कार्य विभाग,
कार्य प्रमंडल, झंझारपुर ।

सेवा में,

अपर मुख्य कार्यपालक पदाधिकारी
—सह— सचिव
ग्रामीण कार्य विभाग,
पटना ।

विषय :

शीर्ष 3054MR योजना अंतर्गत बिहार ग्रामीण पथ अनुरक्षण नीति — 2018 के तहत स्वीकृत कार्यों के आवंटन की मांग के संबंध में।

प्रसंग :

भवदीय पत्रांक मु०अ०-4 (मु०)-3054-04-251/2018-113 अनु पटना दिनांक 10.01.2020

महाशय,

उपरोक्त विषयक प्रासांगिक पत्र के आलोक में शीर्ष 3054MR योजना अंतर्गत बिहार ग्रामीण पथ अनुरक्षण नीति —2018 के तहत स्वीकृत कार्यों में कृत कार्य के भुगतान हेतु विहित प्रपत्र में अधियाचना तैयार कर आवश्यक कार्रवाई हेतु समर्पित की जा रही है।

अतः अनुरोध है कि आवंटन उपलब्ध कराने की कृपा की जाय।

अनु. — विहित प्रपत्र में अधियाचना प्रपत्र

बम्प इन्टिग्रेडर मशीन से लिया गया प्रतिवेदन

विश्वासभाजन



कार्यपालक अभियंता,
ग्रामीण कार्य विभाग, कार्य प्रमंडल,
झंझारपुर

Form GFR 19- A

(See Government of India's Decision (I) below Rule - 150)

Form of Utilization Certificate upto the month July 2025

New Maintenance Policy 2018

Sl. No.	Name of Scheme	Sanction No. & Date with Amount (in lacs)	Amount Received (in lacs)	Particulars
1	1	2645 enc/ Dt. 17.07.2025	9441.85124	Certified that Rs:-9441.85124 Lac received Till the date in favour of Executive Engineer, RWD Work Division Jhanjharpur. A sum of Rs 9199.36279 Lac has been utilized for the purpose of NEW_MR Scheme as given in the margin for which it was sanctioned and that the balance of Rs 242.48825 Lacs remaining .
		Total :	9441.85124	

Certified and verified myself that the conditions on which the grants in aid was sanctioned have been duly fulfilled / are being fulfilled and that I have exercised the following checks to see that the money was actually utilized for the purpose for which it was sanctioned.

Kinds of Checks exercised :-

- Works have been supervised by Executive Engineer/ Superintending Engineer.
- Periodical inspection has been conducted by Executive Engineer/ Superintending Engineer.
- Construction material have been tested.
- Measurements have been recorded in the MBs and test check conducted by the Assistant Engineer/Executive Engineer.
- All other codal formalities have been observed.

Physical Progress achieved :-

- Construction of Road works.
- Construction of CD works


Executive Engineer
RWD works Division
Jhanjharpur

Requisition Format for Scheme Head - MR (3054) Under Bihar Rural Road maintenance Policy 2018 (Initial Rectification and Surface Renewal)

Division : Jhanjharpur

Sl. No	Package no.	Name of Road	Project ID as per MIS	Administrative Approval (AA) Letter No. & Date	Administrative Approval (AA) Length (In Km)	Administrative Approval (AA) Amount (in Lac)	Agreement Amount (in Lac) Initial Rectification with Surface Renewal (in lac)	Agreement Amount (in Lac) 5 years Routine Maintenance (In lac)	Agreement No. & Date	Date of Completion as per Agreement	Actual Date of Completion	Value of IRI (in mm/km)	Thickness of Bitumen Layer (in mm)	Value of Bitumen Content in percentage	Previous Total Allocated Amount (Lac)	up to date expenditure as per MIS (in Lac)	Requisition Against work done (In lac)	Remarks
RM/MA/JHA/25/0002																		
1		Naruaar Janki Bhawan to Kamla Tatbandh	622985555094	1086/01.0 3.2024	0.35	136.60	94.90035	2.74450	06MBD/2024-25/04.02.2025	03-11-2025		2850	25mm	5.0%	90.50000	90.50000	3.65541	Surface Completed
2		Sohpur To Parsa Mahadalit Tol	31909813032	1086/01.0 3.2024	1.027	52.94920	30.13471	8.06565	06MBD/2024-25/04.02.2025	03-11-2025		2800	25mm	5.0%	28.20000	28.20000	0.62710	Surface Completed
3		Rwd Bajrang Bali Asthan To Singh Tol Bema Yadav Tol	31909812042	1086/01.0 3.2024	1.63	97.8581	60.59418	11.0915	06MBD/2024-25/04.02.2025	03-11-2025		2950	25mm	5.0%	0.00000	0.00000	47.54445	Surface Completed
4		Khaira Siwotar Primary School to Mahadalit tola	31909801016	1086/01.0 3.2024	1.65	83.16	54.11032	8.85535	06MBD/2024-25/04.02.2025	03-11-2025		2500	25mm	5.0%	52.00828	52.00828	0.86113	Surface Completed
5		LO52-T02 NH57 TO SARBSIMA (VR052)	31909802160	1086/01.0 3.2024	0.95	61.97	38.51308	5.62936	06MBD/2024-25/04.02.2025	03-11-2025		2800	25mm	5.0%	37.50849	37.50849	0.49244	Surface Completed

Signature
30/08/25
AE

Signature
30/08/25
AE

Signature
30/08/25
AE

Signature
Executive Engineer
RWD Works Division
Jhanjharpur

4100

Name of Customer: Rajhar Yadav, Machine no: 19198, Road: Rwd Bajrang Bali Asthan To Singh Tol Berma Yadav Tol, Date: 09-07-25, Section No: 25, Equation: $Y=1.0216X+165.9$

U/V mm/km

2950

1800

0

0.1

0.2

0.3

0.4

0.5

0.6

0.7

0.8

0.9

1

1.1

1.2

1.3

1.4

1.5

1.6

1.7

Distance*1000 m

[Signature]
30/08/25
AE

[Signature]
30/08/25

[Signature]
02/09/25

Name of work : Rwd Bajrang Bali Asthan To Singh Tol Berma Yadav Tol

Name of customer : Rajdhar Yadav

(R)Rural Road		
Good	Average	Poor
< 4000	4001 - 5000	> 5000

Date	Time	Test No	Distance(m)	Total Distance(m)	BUMP(cm)	Speed(Km/Hr)	U(mm/Km)	Corrected UI (mm/Km)	IRI	Status	Latitude	Direction	Longitude	Direction1	Remarks
09/07/25	10:53:32	25	100	100	22.0 cm	23.6 Km/Hr	2200.0 mm/Km	2413	3.32	Good	26.27689	N	86.336899E	Normal	
09/07/25	10:53:46	25	100	200	24.0 cm	22.7 Km/Hr	2400.0 mm/Km	2618	3.57	Good	26.276088	N	86.337402	E	Normal
09/07/25	10:54:10	25	100	300	28.0 cm	17.1 Km/Hr	2800.0 mm/Km	3026	4.06	Good	26.275189	N	86.33721	E	Normal
09/07/25	10:54:32	25	100	400	30.0 cm	16.3 Km/Hr	3000.0 mm/Km	3231	4.3	Good	26.274399	N	86.337027	E	Normal
09/07/25	10:54:55	25	100	500	27.0 cm	15.6 Km/Hr	2700.0 mm/Km	2924	3.94	Good	26.27205	N	86.337063	E	Normal
09/07/25	10:55:22	25	100	600	28.0 cm	13.4 Km/Hr	2800.0 mm/Km	3026	4.06	Good	26.27257	N	86.337375	E	Normal
09/07/25	10:55:42	25	100	700	28.0 cm	17.6 Km/Hr	2800.0 mm/Km	3026	4.06	Good	26.271702	N	86.336174	E	Normal
09/07/25	10:55:58	25	100	800	28.0 cm	21.8 Km/Hr	2800.0 mm/Km	3026	4.06	Good	26.271111	N	86.334413	E	Normal
09/07/25	10:56:15	25	100	900	28.0 cm	21.6 Km/Hr	2800.0 mm/Km	3026	4.06	Good	26.272133	N	86.333174	E	Normal
09/07/25	10:56:31	25	100	1000	28.0 cm	22.9 Km/Hr	2800.0 mm/Km	3026	4.06	Good	26.275946	N	86.330322	E	Normal
09/07/25	10:56:46	25	100	1100	28.0 cm	23.1 Km/Hr	2800.0 mm/Km	3026	4.06	Good	26.273099	N	86.332862	E	Normal
09/07/25	10:57:01	25	100	1200	26.0 cm	24.0 Km/Hr	2600.0 mm/Km	2822	3.81	Good	26.271643	N	86.334072	E	Normal
09/07/25	10:57:13	25	100	1300	27.0 cm	19.4 Km/Hr	2700.0 mm/Km	2924	3.94	Good	26.271201	N	86.335383	E	Normal
09/07/25	10:57:31	25	100	1400	22.0 cm	20.4 Km/Hr	2200.0 mm/Km	2413	3.32	Good	26.270753	N	86.23863	E	Normal
09/07/25	10:57:31	25	100	1500	22.0 cm	20.4 Km/Hr	2200.0 mm/Km	2413	3.32	Good	26.273435	N	86.336993		
09/07/25	10:57:31	25	100	1600	22.0 cm	20.4 Km/Hr	2200.0 mm/Km	2413	3.32	Good	26.273435	N	86.33699		

30/07/25

30/07/25

30/07/25

अधियाचना हेतु प्रमाण-पत्र

प्रमाणित किया जाता है कि ... NMP - 2018 ... योजनान्तर्गत:-

1. पथ/पुल RWD Barrangbali sthan to Singh Jol में कराये गये कार्य की Verma Yadav Jot गुणवत्ता जांच की गयी है जो निर्धारित मानक/विशिष्टियों के अनुरूप है।
2. अद्यतन कराये गये कार्य की मापी संबंधित मापी पुस्तिका में दर्ज है जिसका सत्यापन कर लिया गया है।

30/08/25 lakhnau
कनीय अभियंता
ग्रामीण कार्य विभाग
कार्य प्रशाखा-lakhnau

30/08/25
सहायक अभियंता
ग्रामीण कार्य विभाग
कार्य अवर प्रमंडल-lakhnau

30/08/25
कार्यपालक अभियंता
ग्रामीण कार्य विभाग
कार्य प्रमंडल-